

**CITY OF ELKO
 BID TABULATION
 FOR
 3RD SECONDARY CLAIPIER -REHAB PROJECT 2019
 DATE: 3/6/19**

Name
 Address
 City State
 Phone No.
 Fax No.

The Gateway Co. of UT
1617 North Chicago St.
Salt Lake City, UT 84116
801-532-2500
801-532-2559

Olympus & Asso. Inc.
405 Lovitt Ln
Reno, NV 89506
775-332-0346
775-322-0288

No.	Bid Item Description	Quantity	Unit	Unit Price	Total Amount		Unit Price	Total Amount	
1	Mobilization & Demobilization Labor, Equipment, and Materials to and from the Project Site @: _____ _____ Per Lump Sum Amount	1	LS	\$ 10,000.00	\$10,000.00		\$2,000.00	\$2,000.00	
2	The Contractor shall Clean the Clarifier Surfaces prior to sand blasting the surfaces using high pressure water jetting equipment, or similar methods @: _____ Per Lump Sum Amount. (Minimum of 3,000 psi and maximum of 5,000.00)	1	LS	\$ 4,500.00	\$4,500.00		\$2,000.00	\$2,000.00	
3	Provide and Perform Abrasive Sand Blast Cleaning meeting SSPC-SP10/NACE 2 "Near White Blast Cleaning" of all Clarifier Submerged Metal Surfaces @: _____ Per Square Foot of Surface Area.	2370	SF	\$ 23.00	\$55,510.00	Should be \$ 54,510.00 (\$1,000.00 error)	\$35.50	\$84,135.00	
4	Provide and Perform Abrasive Sand Blast Cleaning meeting SSPC-SP6/NACE 3 "Commercial Blast Cleaning" of the Metal Bridge Surfaces located above the High Water Level @: _____ Per Square Foot of Surface Area.	340	SF	\$ 18.53	\$6,300.00		Should Be \$ 6,300.20 (.20 off)	\$22.00	\$7,480.00
5	Provide Materials, Labor & Equipment to coat/paint all metal surfaces of the East Clarifier, as specified, @: _____ Per Square Foot of Surface Area.	2710	SF	\$ 9.11	\$24,688.00		Should be \$ 24,688.10 (off .10)	\$23.00	\$62,330.00
6	Third Party NACE Inspection Holiday Testing and DFT Thickness Test & Reports, as specified and described on Page 72 in the Project Technical Specifications @ _____ Per Lump Sum Amount. (revised)	1	LS	\$ 1,600.00	\$1,600.00		\$19,955.00	\$19,955.00	
7	Project Cleanup – Provide all Materials, Labor and Equipment required to clean up the Jobsite after completion of the work – see @: _____ Per Lump Sum.	1	LS	\$ 2,600.00	\$2,600.00		\$2,000.00	\$2,000.00	