



City of Elko Clerk's Department  
1751 College Avenue  
Elko, NV 89801  
(775) 777-7126  
FAX (775) 777-7129

## **ADDENDUM NUMBER TWO**

### WRF REUSE WATER FILL STATION

Please confirm receipt of ADDENDUM NUMBER TWO AND FAX BACK TO (775) 777-7129 or email to [cityclerk@elkocitynv.gov](mailto:cityclerk@elkocitynv.gov).

RECEIVED:

\_\_\_\_\_  
SIGNATURE

\_\_\_\_\_  
COMPANY NAME

Dated this      day of      2018.

Elko City Clerk  
Shanell Owen, MMC

**\*\*\* PLEASE NOTE RECEIPT OF ADDENDUM NUMBER TWO ON  
APPLICABLE LINE ON SUBMITTED BID PROPOSAL \*\*\***

**ADDENDUM NUMBER TWO**  
to the  
**WRF FILL REUSE WATER FILL STATION**  
**BID DOCUMENTS, SPECIFICATION AND PLANS**

---

To all prospective bidders under the specifications for the **WRF Reuse Water Fill Station**, for which bids are to be received by the City of Elko, at the office of the Elko City Clerk located at 1751 College Avenue, Elko, Nevada 89801, until 3:00 P.M., local time, on Friday, February 16th, 2018.

The following changes, deletions and additions are herein made and become a part of the Project Bidding Documents, Specifications and Plans for the above referenced Project.

- 1) The following question was asked:

*“Is there any suitable fill material available onsite for the borrow embankment: if so, how far away is it located?”*

**Response:** There is a stock pile of material located approximately 1000 feet south of the WRF Office that may be suitable for use. This pile can be viewed by contacting Mike Haddenham 775-777-7386. If the contractor is interested in using this material the same submittal requirements that are required for off-site borrow embankment will be required for used of the stockpile. There is no guarantee the stock pile will meet the specifications and therefore be suitable for use. All borrow material regardless of origination will be required to meet the requirements for Structural Fill Section 200.01.09 of the Standard Specifications. The successful Contractor will be responsible for the appropriate submittals for the Engineer’s review prior to bringing the material on-site. Additionally, the stock pile does have some debris that would need to be removed and the amount of the stock pile may or may not be enough for this project. Other stockpiles located south of the intersection of Hot Springs Road and Sewer Treatment Plant Road are not suitable for use.